



- 3.3.2.3.1 Concrete strength will be considered potentially deficient if the averages of two consecutive sets of strength test results fail to equal or exceed the specified strength or if any individual strength test result falls below the specified strength or if any individual strength test result falls below the specified strength. Testing may be required as directed by the Architect/Engineer
- 3.3.2.3.2 Concrete work not having the required strength, as determined by the Architect/Engineer, shall be replaced at the Contractor's expense.
- 3.3.2.3.3 All costs incurred in providing the additional testing and/or analyses required as a result of deficient concrete shall be at the Contractor's expense. All costs as a result of delays due to additional testing and/or analyses will be at the Contractor's expense, with no extension of contract length, regardless of the outcome of the testing

3.4